

15-007-20613-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County. Sec. 32 Twp. 31 Rge. 12w E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE SW


Lease Owner George R. Jones  
Lease Name Bedwell Well No. 1  
Office Address 125 N. Market Suit 1310 Wichita Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Gas Not enough for commercial  
Date Well completed 4/23 19 78  
Application for plugging filed 7/25 19 78  
Application for plugging approved 7/26 19 78  
Plugging commenced 7/31 19 78  
Plugging completed 8/11 19 78

Reason for abandonment of well or producing formation  
No gas pressure  
If a producing well is abandoned, date of last production  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well WM. T. Owen  
Producing formation \_\_\_\_\_ Depth to top 4196 Bottom 4220 Total Depth of Well 4220  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS DIVISION CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>8.15.78</u>	<u>Surface</u>	<u>0</u>	<u>268</u>	<u>8 5/8</u>		
		<u>0</u>	<u>4197</u>	<u>4 1/2</u>		<u>3378</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 50 sx. cement with halliburton to 3583

Pumped 20 jell and 100 sx.cement 3% C.C. with Halliburton finished at 550 # pres

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling  
Box 373 Geneseo Kansas 67444

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_, (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 14<sup>th</sup> day of August, 1978

Steven K Prickett  
Notary Public.

My commission expires August 20, 1978  
STATE NOTARY PUBLIC  
**STEVEN K. PRICKETT**  
Rice County, Ks.  
My Comm Exp Aug 20, 1978

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

APR 21 1978

Bedell #1  
 C-SE-SW Sec 32-31S-12W  
 Barber County Kansas

Commenced: 4-2-78

Completed: 4-10-78

OPERATOR: GEORGE R. JONES

Depth		Formation	Remarks
From	to		
0	5	Surface Soil	Ran 7 jts of 200 8 5/8" csg set @ 286' Cemented w/ 225 sks Common 2% Gel 3% CC PD @ 1:30 a.m. 4-3-78
5	291	Shale-Sand	
291	1690	Redbed	Ran 134 jts of 10 1/2" 4 1/2" csg set @ 4197' Cemented w/ 125 sks Reg Posmix 18% Salt 1% CFR-2 PD @ 9:20 a.m. 4-10-78
1690	1875	Shale-Lime	
1875	2405	Lime-Shale	
2405	2600	Shale-Lime	
2600	2831	Lime-Shale	
2831	3250	Shale-Lime	
3250	3472	Lime-Shale	
3472	3740	Shale-Lime-Sand	
3740	4092	Lime-Shale	
4092	4220	Lime	
	4220 - TD		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above  
 Drillers' Well Log is true and correct to the best of my knowledge and belief and  
 according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 20th day of April, 1978.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 9, 1979.



APR 25 1978