


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 7 Twp. 34S Rgd. 10W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner MULL DRILLING CO. INC.
Lease Name GRIFFEN Well No. 1
Office Address 6405 East Kellogg Wichita Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 23 19 57
Application for plugging filed July 23 19 57
Application for plugging approved July 23 19 57
Plugging commenced July 23 19 57
Plugging completed July 23 19 57
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives
Producing formation none Depth to top none Bottom Total Depth of Well 5099 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	240 ft	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy rotary mud from TD back to 235. Plug set at 235, 35 sacks of cement on top of plug. Mud on top of cement plug set at 40ft. and 15 sacks of cement on top. Pipe cut off 4 ft. below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co Tools
Address

STATE OF KANSAS, COUNTY OF Harper, ss.

O. C. Arnett (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *O.C. Arnett*
Attica, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24 day of July, 19 57

My commission expires Jan. 7, 1961
Maxine McGuire, Notary Public.

24-7368-S 3-53-20M

RECEIVED
STATE CORPORATION COMMISSION
07-25-1957
JUL 25 1957

PLUGGING
FILE SEC. 7 T. 34 R. 10W
BOOK PAGE 31 LINE 4

CONSERVATION DIVISION
Wichita, Kansas

15-007-00365-00-00

ROTARY DRILLERS LOG

COMPANY : Mull Drilling Company, Inc.
Wichita, Kansas

ROTARY DRILLING COMMENCED: 7-5-57

CONTRACTOR : Mull Drilling Company, Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 7-23-57

CASING RECORD : Set 8 5/8" @ 240' cemented
with 150 sacks cement.

LOCATION: Griffin #1
SE SE SE of Sec. 7-34S-10W
Barber County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Clay	100
Red Rock	240
Red Bed	1130
Shale & Shells	1525
Shale & Lime	4203
Lime	4528
Lime & Shale	4658
Lime	4851
Shale & Lime	4892
Shale	5001
Shale & Lime	5070
Simpson Sand	5099 R.T.D.


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

BY Joseph B. Brungardt, Jr. ASST. PRES.
JOSEPH B. BRUNGARDT, JR.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 8th day of August, 1957.



Madon T. Miller
NOTARY PUBLIC

RECEIVED
CORPORATION COMMISSION

DEC 24 1957

CONSERVATION DIVISION
Wichita, Kansas

12-24-1957

PLUGGING
FILE SEC. 7 T. 34 R. 10W
BOOK PAGE 31 LI E 4