

15-007-00022-00-00


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barber County, Sec. 5 Twp. 34S Rge. (E) 10 (W)

Location as "NE/CNW&SW&" or footage from lines. NW NW NE  
Lease Owner Stelbar Oil Corporation, Inc., & Wilcox Oil Company  
Lease Name Circle Well No. 1  
Office Address 310 Petroleum Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed July 7, 1960  
Application for plugging filed July 7, 1960  
Application for plugging approved July 7, 1960  
Plugging commenced July 7, 1960  
Plugging completed July 7, 1960  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4706 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	275'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud to 240', dumped 20 sacks cement, filled with mud to 35', set plug and dumped ten sacks cement, steel plate welded on surface.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1960

CONSERVATION DIVISION  
Wichita, Kansas

07-15-1960

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Stelbar Oil Corporation, Inc.  
Address 310 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester  
310 Petroleum Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1960

My commission expires January 18, 1964

Leona Hargrove  
Notary Public.



15-007-00022-00-00

LOG

Farm: Circle  
Well No. 1  
NW NW NE 5-34S-10W  
Barber County, Kansas

Drilling Commenced: 6-22-60  
Drilling Completed: 7-7-60  
Owner: Stelbar Oil Corp., Inc., and  
Wilcox Oil Co.  
Contractor: Stelbar Oil Corporation, Inc.

8-5/8" 275' cemented with 200 sacks 6-23-60

Elevation: Est. 1434 DF

0	65	Surface Clay
65	275	Broken Lime
275	1600	Shale & Shells
1600	1824	Lime & Shale
1824	1835	Shale
1835	1975	Shale & Lime
1975	2069	Shale & Shells
2069	2185	Shale & Lime
2185	3020	Shale & Shells
3020	3159	Shale & Lime
3159	3305	Sandy Lime
3305	3673	Lime & Shale
3673	4188	Shale & Shells
4188	4367	K. C. Lime
4367	4431	Lime
4431	4601	Lime & Shale
4601	4706	Mississippi Lime
		D & A

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1960

CONSERVATION DIVISION  
Wichita, Kansas

07-15-1990