

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34621 Name: Renda Energy Address 1: 2525 McKinney Ave Address 2: Suite B City: Dallas State: TX Zip: 75201 Contact Person: Preston Cheng Phone: (214) 731 9208 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 077-21758-00-00 Spot Description: Sec. 35 Twp. 34 S. R. 5 East West 330 Feet from North South Line of Section 200 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Harper Lease Name: Sheen Well #: 1-35 Date Well Completed: 04/01/2012 The plugging proposal was approved on: 9/16/2013 (Date) by: Steve Bond (KCC District Agent's Name) Plugging Commenced: 9/26/2013 Plugging Completed: 9/27/2013

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Formation, Content, Casing, Size, Setting Depth, Pulled Out. Header: Oil, Gas or Water Records / Casing Record (Surface, Conductor & Production)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

see attached

KCC WICHITA DEC 16 2013 RECEIVED

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage Inc. Address 1: 1125 Main Address 2: City: Chase State: KS Zip: 67524 Phone: (620) 938 - 2943 Name of Party Responsible for Plugging Fees: Lasso Energy, LLC

State of Kansas County, Chase, ss.

Paul Cheng (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

Date	Invoice #
10/28/2013	14168

Bill To
Lasso Energy, LLC P.O. Box 465 Chase, Kansas 67524

P.O. No.	Lease	County
	Sheen I-35	Barber

Qty	Description	Rate	Amount
37	Hrs	195.00	7,215.00T
4	Nights Out of Town	210.00	840.00T
	Casing Knife	250.00	250.00T
	5 Sx Cement	60.00	60.00T
	Mike' s Testing - Lease Cost	5,000.00	5,000.00
	Copeland - Cement	4,072.95	4,072.95
	WhiteLightning - Tested tubing	1,192.00	1,192.00
	LogTech - Set BP	1,817.00	1,817.00
	9/14/13 Set rig in. Rigged up for rods. Laid out 100 7/8 in singles. 3hrs		
	9/15/13 Laid out 94 rods. Rigged over. Laid out 152jts of 2-7/8 tubing. Tore rig down and moved off. 13hrs		
	9/26/13 Set rig in. Set BP @ 4640'. Dumped 5sx cement with bailer. Dug out cellar and pit. Set casing jacks in. Pulled stretch, 30". Cut casing @ 3300'. Shut down. 10hrs		
	9/27/13 Pulled 5-1/2 casing to 950'. Rigged up Copeland. Pumped 35sx 60/40poz 6% gel. Pulled up to 450', circulated cement to surface with 200sx 60/40poz 6% gel. Pulled rest of casing. Tore down and moved off. 11hrs		
	KCC: Steve Van Gieson Sales Tax		
		KCC WICHITA	598.10
		DEC 16 2013	
		RECEIVED	
		Total	\$21,045.05