


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217



Locate well correctly on above
Section Plat

Barber County, Sec. 3 Twp. 34S Rge. 13W (E) 660' (W)
Location as "NE/CNW&SW" or footage from lines G-SE-SE
Lease Owner Harper Oil Company
Lease Name Donovan Well No. 1
Office Address 904 Hightower Building, Oklahoma City, Oklahoma 73102
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed _____ 19____
Application for plugging filed March 14, 1974
Application for plugging approved March 18, 1974
Plugging commenced _____ 19____
Plugging completed 8:30 A.M. March 14, 1974
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstine
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Elgin Sand	water	3679	3843	8 5/8	313'	0
Lansing	no test	4094				
Mississippi	tite	4707				
Viola	no test	5068				
Simpson Sand	Prob. water	5192	5222			
	no test					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged by Allied cementing under the direction of Gabbert-Jones with 35 sacks at 275', 13 sacks at 40' and 2 sacks in rat hole. Job completed at 8:30 A.M. 3/14/74. k State plugging Russell Biberstine.

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
E. A. BOYDSTON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. A. Boydston
904 Hightower Bldg, Okla. City, Okla. 73102
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of March, 1974

Billie K. Schmetler
Notary Public.

My commission expires October 12, 1974
My commission expires _____

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

DONOVAN #1
 SE/4 SE/4
 Sec. 3-34S-13W
 Barber County, Kansas

COMMENCED: February 27, 1974
 COMPLETED: March 14, 1974

OPERATOR: HARPER OIL COMPANY

DEPTH		FORMATION	REMARKS
From	To		
0	325	Shale-Shells	Ran 16 jts. of 28# 8-5/8" csg. set @ 323' cemented w/275 sacks common cement, 2% Gel, 3% CC. P.D. @ 10:30 AM. 2-28-74.
325	700	Shale	
700	1338	Shale-Shells	
1338	1850	Shale	Dry and Abandoned.
1850	1920	Shale-Lime	
1920	2025	Lime-Shale	
2025	2270	Shale-Shells	
2270	3160	Shale-Lime	
3160	3575	Lime-Shale	
3575	3705	Shale-Lime	
3705	3845	Sand	
3845	3890	Shale	
3890	4035	Shale-Lime	
4035	4315	Lime-Shale	
4315	4485	Lime	
4485	4570	Lime-Shale	
4570	4960	Lime	
4960	5024	Shale	
5024	5118	Lime	
5118	5174	Lime-Shale	
5174	5189	Lime	
5189	5230	Sand	
5230	5250	Shale	

RECEIVED
 STATE CORPORATION COMMISSION
 APR 22 1974
 CONSERVATION DIVISION
 Wichita, Kansas

5250 Total Depth

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the SE/4 SE/4 of Sec. 3-34S-13W, Barber County, Kansas to the best of my knowledge and belief.

James S. Sutton II
 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 20th day of March, 1974, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
 MARJORIE HALL - NOTARY PUBLIC

My Commission Expires: November 29th, 1975.

