

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION REVISION 15-80

FEB 9 1983

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 20 TWP. 30S RGE. 15W E/W
Location as in quarters or footage from lines:
2310 FSL - 990 FEL

Lease Owner TXO Production Corp.
Lease Name Gibson "C" Well No. 1
Office Address 200 W. Douglas, Suite 300, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed January 27, 1983
Application for plugging filed February 8, 1983
Plugging commenced January 27, 1983
Plugging completed January 27, 1983
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Permission was obtained:

Name of Conservation Agent who supervised plugging of this well Steve Durrant of Dodge City
Producing formation Depth to top bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	1031'	24	25 jts. k-55	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

The Gibson C-1 was plugged with 130 sx cement, 50/50 poz
4% gel, 3% cc. Plugs were staged at: 50sx at 1800', 50sx
at 1020', 10sx and a solid plug at 40', 10sx in rat and
10sx in mouse hole. Dowell of Pratt was in charge of
cementing and steve durrant of dodge city gave plugging
orders. Final plug was down at 5:30 a.m. on 1-27-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell of Pratt, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Mary Kay Oeding (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) *Mary Kay Oeding*
453 S. Webb Rd., P.O. Box #8611
Wichita (Address) Kansas

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1983

Kathleen G. Quinn
Kathleen G. Quinn Notary Public.

My Commission expires: March 20, 1983



ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

RECEIVED
STATE CORPORATION COMMISSION

FEB 9 1983

CONSERVATION DIVISION
Wichita, Kansas

W E L L L O G



WELL NAME: Gibson "C" #1

WELL LOCATION: SE/4, 20-30S-15W

Barber County, Kansas

COMMENCED: January 14, 1983

COMPLETED: January 27, 1983

CASING RECORD: 8 5/8" set at
1031'

OPERATOR: TXO Production Corp.

CONTRACTOR: Aldebaran Drilling Co., Inc.

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>
RED/BED	0	2460'
LIME & SHALE	2460'	4700'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
SE/4, Sec. 20-30S-15W, Barber County, Kansas TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

Mary Kay Oeding
Mary Kay Oeding, Accountant
February, 1983

SUBSCRIBED AND SWORN TO BEFORE ME THIS 8th DAY OF February, 1983

MY APPOINTMENT EXPIRES: March 20, 1983

KATHLEEN G. QUINN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 3-20-83

Kathleen G. Quinn
Kathleen G. Quinn NOTARY PUBLIC