


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 4 Twp. 30 Rge. 15 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner Purcell-Mull Drilling Co., Inc.  
Lease Name Moffett Well No. 1  
Office Address 6405 E. Kellogg, Wichita 18, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4-16-55 19  
Application for plugging filed 4-16-55 19  
Application for plugging approved 4-16-55 19  
Plugging commenced 4-16-55 19  
Plugging completed 4-16-55 19  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives  
Producing formation None Depth to top Bottom Total Depth of Well 4825 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8 5/8"	421'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy rotary mud. Plug set at 400'. 30 sacks of cement on top of Plug. Mud on top of cement, plug set at 40'. 20 sacks of cement on top. Pipe cut off 3 feet below surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company Tools  
Address 6405 E. Kellogg, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Frank H. Purcell (employee of owner) or (owner of operation) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
6405 E. Kellogg, Wichita 18, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 55

My commission expires January 28, 1957

[Signature] Notary Public.

PLUGGING  
FILE NO. 4-1308-15W  
PAGE 12 OF 15

APR 28 1955  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY DRILLERS LOG

COMPANY: Purcell-Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMMENCED: 3-29-55

CONTRACTOR: Purcell-Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMPLETED: 4-16-55

CASING RECORD: Set 421' of New 8 5/8" Surf. Cas. cemented with 300 sacks cement

LOCATION: Moffett #1  
SE SE SE of Sec. 4 - 30S-15W  
Barber County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

Sand	200	Lime	3736
Red Bed	421	Lime & Shale	3716
Red Rock, Shale & Shells	725	Sand	3995
Red Bed & Shells	900	Shale & Sand	4057
Shale & Shells	1310	Lime	4565
Shale, Shells & Salt	1810	Lime & Shale	4605
Shale & Shells	2000	Lime	4644
Lime & Shale	2215	Lime & Chert	4680
Lime	2315	Lime & Shale	4709
Lime & Shale	2521	Shale & Lime	4753
Shale & Lime	2637	Shale & Sand	4761
Lime & Shale	2778	Shale & Lime	4769
Shale & Lime	3263	Lime & Sand	4795
Lime & Shale	3672	Shale & Arkusio	4825 R.F.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

PURCELL-MULL DRILLING CO., INC.

BY *Frank H. Purcell* SECRETARY  
FRANK H. PURCELL

STATE OF KANSAS     )  
                          ) 23  
COUNTY OF SUDWICH )

Subscribed and sworn to before me this 24th day of April, 1955.

*Ernest Zimmerman*  
NOTARY PUBLIC

BY COMMISSION EXPIRES: JANUARY 28, 1957.

PLUGGING  
WY SEC # 30S-15W  
WY W-12-15