

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,221-00-00

LEASE NAME LEE

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 ^{C. NE NW} TWP. 30 RGE. 15 (XXXr(W))

COUNTY BARBER

Date Well Completed

Plugging Commenced 11-19-91

Plugging Completed 11-25-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR GOULD OIL, INC.

ADDRESS 110 NORTH MARKET #411 WICHITA, KS. 67202

PHONE#(316) 265-5523 OPERATORS LICENSE NO. 5298

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-22-91 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation VIOLA Depth to Top Bottom T.D. 4890

Show depth and thickness of all water, oil and gas formations. PERFS: 4592-96
4662-72

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				3/4 rods		182 rods.
				2 3/8 tbg.		146 joints
		0	239	8 5/8	239	0
		0	4889	5 1/2	4889	2101 ft., 51 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

TO LOCATION, RIGGED UP, PULLED RODS & TUBING OUT OF THE WELL. DUMPED SAND AND 5 SX CEMENT. SHOT OFF CASING AT 2101 FT., AND PULLED 51 JTS. TOP OF SAND: 4500 FT. FOR TOP HOLE PLUG, 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8 PLUG, 100 SX CEMENT, 60 40 POZ 6% GEL, 600# MAX, 200# SHUT IN PRESSURES.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) To PWS, Inc.



RECEIVED SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 91
 STATE CORPORATION COMMISSION Dorothy M. Ferguson
 Notary Public

DEC 03 1991 Commission Expires February 6, 1992