

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,520-00-00

LEASE NAME LEE

WELL NUMBER B-1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line
 C SW NE

SEC. 4 TWP. 30 RGE. 14 (XXX) (W)

COUNTY ~~BARBER~~ BARBER

LEASE OPERATOR GOULD OIL, INC.

ADDRESS 110 NORTH MARKET, #411 WICHITA, KS. 67202

PHONE#(316 265-5523 OPERATORS LICENSE NO. 5298

Date Well Completed

Character of Well OIL

Plugging Commenced 11-13-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-25-91

The plugging proposal was approved on 11-22-91 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filled? YES If not, is well log attached?

Producing Formation VIOLA Depth to Top Bottom T.D. 4900

Show depth and thickness of all water, oil and gas formations. PERFS: 4660-64

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				3/4 rods		188 rods
				2 3/8 tbg		155 jts. of tubing
		0	286	8 5/8	286	0
		0	4898	5 1/2	4898	1972' 47 JTS. CASING

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

TO LOCATION, RIGGED UP, PULLED RODS AND TUBING, DUMPED SAND & CEMENT: TOP OF SAND 4600 FT.

SHOT OFF CASING AT 1972 FT, PULLED 47 JOINTS. TOP HOLE PLUG: 300# HULLS, 10 SX GEL, 50

SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8 PLUG, 100 SX CEMENT, 60 40 POZ, 6% GEL.

1000# MAX PRESSURE, 200# SHUT IN PRESSURE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P.O. BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt Well Service, Inc.



RECEIVED

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 91

Dorothy M. Furgason
 Notary Public

STATE CORPORATION COMMISSION

My Commission Expires: February 6, 1992

DEC 03 1991