

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County. Sec. 16 Twp. 30 Rge. 15 (E) W. (W)

Location as "NE/CNW/SW" or footage from lines 330' N. & 330' W. of SE Cor.

Lease Owner Cities Service Oil Company

Lease Name Walker "B" Well No. 1

Office Address Box 144, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 17 1958

Application for plugging filed November 17 1958

Application for plugging approved November 17 1958

Plugging commenced November 17 1958

Plugging completed November 17 1958

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19-

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 464 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	909'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

464-300', heavy mud.
300-240', 1/4 sack hulls, wood plug and 20 sacks cement.
240-35', heavy mud.
35' to base of cellar, 1/4 sack hulls, wood plug and 10 sacks cement.

STATE OF KANSAS
COMMISSION
DEC 6 1958 12:6:58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address Box 359, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November 1958
W. D. Smith
Notary Public.

My commission expires March 12, 1959.

PLUGGING
FILE SEC. 16 T. 30 R. 15 W.
BOOK PAGE 146 LINE 8

WELL RECORD

WILDCAT.....
 DISCOVERY.....
 POOL.....
 COMPANY Cities Service Oil Co. WELL # 1 FARM Walker "B"
 LOCATION 330' North and 330' West of SE Corner
Section 16, Township 30, Range 15 N.
 ELEV. 1869 (1866 Cr.) CO. Barber STATE Kansas
 IP. Dry hole. P. A. A. November 17, 1958
 PERFS.....
 FRAC..... ACID None
 T.D. 4644' P.B.T.D..... GRAV/GOR.....
 DRLG. COMM. October 26, 1958 COMP. Nov. 16, 1958 CONTRACTOR Peel Bros.

CASING RECORD:

8-5/8" at 909' with 600 sacks cement.

FORMATION RECORD:

clay, shale and shells	0-205
shale, red bed and shells	615
shale and shells	911
lost circulation at 736'	
red bed and shale	1160
shale and shells	1850
shale	1985
shale and lime	2050
lime	2100
lime and shale	2520
shale and lime	2640
lime and shale	2800
shale and lime	3070
lime	3185
lime and shale	3315
lime	3545
lime and shale	3650
shale and lime	3905
lime	3965
lime and shale	4010
lime	4086
lime and shale	4155
lime	4205
lime and shale	4230
lime	4314
lime and shale	4338
lime	4394
lime and shale	4420
lime	4620

Heebner	3791
Dodge	3808
Douglas	3830
Brown Limestone	3952
Lansing	3969
Base Kansas City	4375
Cherokee Sand	4485
Mississippi	4522
Viola	4556
Pen.	89'
T.D.	4644'

D.S.T. 4550-64, open 1 hr., rec. 15' mud;
 B.H.P. 0/ in 30 minutes.
 D.S.T. 4564-75, open 1 hr., rec. 26' mud;
 B.H.P. 0/ in 30 minutes.
 D.S.T. 4574-85, open 1 hr., rec. 25' mud;
 B.H.P. 45/ in 30 minutes.
 D.S.T. 4584-92, open 1 hr., rec. 35' mud;
 B.H.P. 62/ in 30 minutes.
 D.S.T. 4591-4610, open 1 hr., rec. 22' mud;
 B.H.P. 57/ in 30 minutes.

Slope Tests (Syfo):

500'	-	0°
1000'	-	0°
1500'	-	1°
2250'	-	1°
2500'	-	1°
3000'	-	1°
3500'	-	1°
4230'	-	1°

PLUGGING

FILE SEC 16 T 3 OR 15 W

BOOK PAGE 146 LINE 8

lime and chert 4634
 cherty lime 4644 T.D.