

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber

County. Sec. 9 Twp. 30S Rge. (E) 15 (W)

Location as "NE/CNW%SW%" or footage from lines NE/4 NE/4 SE/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Moffett Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed January 25 1955
Application for plugging filed September 21 1957
Application for plugging approved September 23 1957
Plugging commenced September 30 1957
Plugging completed October 6 1957
Reason for abandonment of well or producing formation Reservoir depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production July 15 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation Pennsylvania Sand Depth to top 4568 Bottom 4590 Total Depth of Well 4838 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 233' | none |
| | | | | 5 1/2" | 4838' | 3902' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 4560',
dumped 5 sax cement @ 4560' w/dump bailer.
Top of cement, 4530'. Pumped in 50 sax Gel-Mud
@ 1800' by Globe Cementing Co. Filled hole w/mud
to 230', set rock bridge, dumped 20 sax cement.
Top of cement, 170', filled hole w/mud to 35',
set rock bridge, dumped 10 sax cement for cap.

37
RECEIVED
OCT 17 1957
CONSERVATION DIVISION
Wichita, Kansas
10-17-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address P. O. Box 711, Great Bend, Kansas - License #12

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 1957
Barbara J. Scott
Barbara J. Scott, Notary Public.

My commission expires December 1, 1960

PLUGGING
FILE SEC. 9 T. 30 R. 15W
BOOK PAGE 47 LINE 17

NO. 1 MUFFETT

WELL RECORD

Location: NE NE SE, 9-308-15W
Barber County, Kansas

Commenced: December 31, 1954

Operator: Graham-Messman-Rinehart Oil Company
1005 East Second, Wichita, Kansas

Completed: January 14, 1955

Elevation: ¹⁹⁶⁷ 1984 KB

Contractor: Graham-Messman-Rinehart Drilling Co.
1005 East Second, Wichita, Kansas

Production: Gas

Casing Record: 8 5/8" @ 233' w/150 sacks cement
5 1/2" @ 4838' w/100 sacks cement

....L O G....

| | |
|----------------------|-------------|
| Sand-Clay | 80 |
| Red Bed-Shale | 233 |
| Red Bed-Shells | 930 |
| Red Bed-Shells-Shale | 1532 |
| Shale | 2184 |
| Lime-Shale | 3825 |
| Lime-Shale-Sand | 3981 |
| Sand-Shale | 4080 |
| Limo-Sandy Shale | 4190 |
| Lime | 4379 |
| Lime-Shale | 4439 |
| Lime | 4535 |
| Lime-Shale | 4585 |
| Lime-Chert | 4737 |
| Lime | 4802 |
| Shale | 4818 |
| Arbuckle lime | 4838 R.T.D. |

Datum not changed

Sample Tops

Log Tops

| | |
|--------------------------|--------------------------|
| Heebner 3871 (-1887) | Heebner 3872 (-1882) |
| Douglas 3908 (-1924) | Douglas 3909 (-1925) |
| Brn Lime 4047 (-2063) | Brn Lime 4050 (-2066) |
| Lansing 4064 (-2080) | Lansing 4066 (-2082) |
| Penn. Sd. 4566 (-2582) | Penn. Sd. 4568 (-2584) |
| Viola 4590 (-2606) | Viola 4590 (-2606) |
| Simpson Sh. 4735 (-2751) | Simpson Sh. 4739 (-2755) |
| Simpson Sd. 4774 (-2790) | Arbuckle 4819 (-2835) |
| Arbuckle 4818 (-2834) | |

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: *J. H. Gilliland*
J. H. Gilliland

Subscribed and sworn to before me this
25th day of January 1955.

James L. Davis
Notary Public

My Commission Expires: November 5, 1958

RECEIVED
STATE CORPORATION COMMISSION
GMR
File Copy

OCT 17 1957

copy to KGB 1-27-55

PLUGGING
FILE SEC 9 T 30 R 154
BOOK PAGE 47 LINE 17