

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -009- 2111-0000 (of this well)

Operator's Full Name Sid Tomlinson
Complete Address Box 594 Twin Falls, Idaho 83301
Lease Name Peschka Well No. 1
Location 100' E SW SW NE Sec. 34 Twp. 16 Rge. 13 00X (W)X
County Barton Total Depth 3430'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 12:15 PM Day 4 Month 9 Year 1979

The above well was plugged as follows:

Sanded back to 3260' and 5 sx cement with dump bailer.
Squeezed thru 8 5/8" surface casing with 4 sx hulls,
25 sx mud gel, plug, and 100 sx cement.
Max pres. 1200#. Shut in pres, 400#.
Recovered 2335' of 5 1/2" casing.
Plugged back to 3407', top perforations at 3307'.
3427' of 5 1/2" casing cemented with 125 sx cement.
365' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION
SEP - 5 1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Dwain Rankin
Well Plugging Supervisor

INVOICED
DATE 9-6-79
INV. NO. 0376-W