

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1962

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dec. 9, 1962.

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Caseing Pulling Inc. has this date requested permission to plug the following described well:

Mr. D. B. Pully guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Co.

Complete Address: Box 1070 Great Bend, Kansas.

Lease Name: Sterling "A" #1 Well No. #1

Location: G-N/2-SE-SE Sec. 29 Twp. 34 Rge. 13 (E) (W)

County Barber County Total Depth 3641 ^{Abandoned} Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

3630' of 7" long string cemented with 200 sacks cement.
Hole sanded to 3620' & 6 sacks cement. 295' of 10 3/4" surface pipe circulated with cement. Hole filled to 200' with mud, 10' rock bridge & ³⁰ ~~20~~ sacks cement. Hole filled to 40' with mud. 10' rock bridge & ¹⁵ ~~10~~ sacks cement to base of cellar.

Very truly yours,

Herman J.ustus
Conservation Division Agent