

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ted Dix of Skelly Oil Company has this
date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name: Roberts "A" Well No. # 1

Location: SE NE SW Sec. 29 Twp. 34 Rge. 13 (E)(W) W

County Barber Total Depth 4907' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dix was instructed to plug the well as follows:

373' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 300', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 saks.

Very truly yours,

Archie Elving

Conservation Division Agent