



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 1 1963

4-163
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Smith of Glen & Smith Pipe Pulling has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corporation Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name: Kiras Well No. # 1

Location: SW SW NE Sec. 2 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4553 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

322' of 8 5/8" surface pipe cement circulated. 4547' of
5 1/2" long string cemented with 100 sacks. Plugged back to
4470'. Top perforation 4425'. Sand to 4415' cement with
5 sacks. Fill hole with mud to 200'. 10' rock bridge,
cement with 20 sacks. Fill hole with mud to 40'. 10' rock
bridge cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving
 Conservation Division Agent