

State of Kansas



CP

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-2-68
APR 2 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

March 29, 1968

Dear Sir:

Mr. Russell Hoberrecht of Rusk Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Hoberrecht guarantees payment of the plugging fee.

Operator's full Name: Bower Drilling Co. Inc.

Complete Address: 1434 Wichita Plaza Wichita, Kansas.

Lease Name: Ayers Well No. #1

Location: NE-NW-NE Sec. 2 Twp. 30 Rge. 14 (E)(W) W

County: Barber Total Depth 4585' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberrecht was instructed to plug the well as follows:

4583' of 4 1/2" long string. Top perforation at 3226'. Sand to 3200 ft.
and 3 sacks cement. 372 ft. of 8 5/8" surface pipe circulated
with cement. Mud to 350', 10 ft. rock bridge & 25 sacks cement.
Mud to 40 ft. 10 ft. rock bridge & 10 sacks cement to surface.

Very truly yours,

Harmon J. Gustaf
Conservation Division Agent