



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1962
9-13-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas.

Dear Sir:

I have this date Aug. 31, 1962, 1962, authorized
 the following plugging operation:

Operator's full Name: Jones Gebert, Oil Co.

Complete Address: 1007 Central Bldg. Wichita, Kansas.

Lease Name: Wheat #1 Well No. 1

Location: C SE SW Sec. 4 Twp. 31S Rge. 11 (E) (W)

County Barber Total Depth 4895'

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

350' of 8 5/8" surface pipe circulated with cement. Hole
filled to 200' with heavy drilling mud, 1 sack hulls, 1st
cementing plug and 20 sacks cement through drill pipe.
Hole filled to 35' with heavy drilling mud, 1 sack hulls
2nd cementing plug and 10 sacks cement to base of cellar.
rat hole bridged and 2 sacks cement.

Very truly yours,

 Conservation Division Agent