

NOV 28 1962

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Nov. 22, 1962.

Dear Sir:

Mr. Albert Unruh of Southwest Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Albert Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum INC.  
~~Southwest Caseing Pulling Co.~~

Complete Address: R.R. # 2  
~~Box 364 Great Bend, Kansas.~~

Lease Name: Sterling "B" #1 Well No. #1

Location: C W/2 SW NE Sec. 34 Twp. 34 Rge. 13 (E) (W) X

County Barber Total Depth 3646' Oil Well Abandoned

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

3645' of 4 1/2" long string cemented with 75 sacks cement and 3 sacks gel. Perforated between 3639' and 3642'. Sanded to 3630' & 3 sacks cement. 314' of surface pipe circulated with 200 sacks cement. Hole filled to 200' with mud, 10' rock bridge and 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

*William J. Justice*  
 Conservation Division Agent