

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

R VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Unruh of Southwest Casing Pullinghas this
 date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Roberts "B" Well No. # 1

Location: NE NW SE Sec. 34 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 4881 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

304' of 8 5/8" surface pipe, cement circulated with 225 sacks.

3900' of 5 1/2" long string, cemented with 100 sacks. Plugged

back to 3790'. Top perforation 3661'. Sand to 3650', cement

with 5 sacks. Fill hole with mud to 225', 10' rock bridge,

cement with 20 sacks. Fill hole with mud to 40', 10' rock

bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent