

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 3 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Nov. 22, 1962.

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Caseing Pulling Co. this date requested permission to plug the following described well:

Mr. Albert Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: R. R. #2 Great Bend, Kansas.

Lease Name: Houston "C" #2 Well No. #2

Location: C-E/2 SE NW Sec. 34 Twp. 34 Rge. 13 (E) (W) X

County Barber Total Depth 3648' Oil Well Abandoned

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

3647' of 4 1/2" long string cemented with 75 sacks cement & 3 sacks gel. Perforated between 3643' & 3646'. Sanded to 3630' and 3 sacks cement. 310' of 8 5/8" surface pipe circulated with 175 sacks cement. Hole filled with mud to 200', 10' rock bridge, 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge, and 10 sacks cement to base of cellar.

Very truly yours,

Herbert J. Foster
 Conservation Division Agent