



JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Unruh of Kelso Casing Pulling has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Cities Service Company

Complete Address: 800 Sutton Place Bldg. 209 E. William Wichita, Ks.

Lease Name: Lambert Well No. #1-A

Location: C/ NW NW Sec. 4 Twp. 30S Rge. 13W (E)(W) W

County: Barber Total Depth 4760 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

302' - 8 5/8" csg. set W/ 325 sxs

4448' - 5 1/2" set W/150 sxs PB to 4394'

Perfs 4361 to 4365' SB to 4350 Mixed & run 5 sxs W/ bailer

Pumped 15 gel 6 hulls 10 gel

Released plug & displaced W/ 125 sxs 50/50 poz 4% gel 3% cc

Recovered 3290' of 5 1/2" csg. Very truly yours,
SIP 200# Cemented by Dowell

W. T. Leslie
Conservation Division Agent