

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY O. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Laverentz Well No. # 1

Location: C NE NW Sec. 21 Twp. 30 Rge. 11 (E) (W) W

County Barber Total Depth 4850' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

262' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40'; 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent