



15-009-15982-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg.
212 N. Market
WICHITA, KANSAS 67202

RECEIVED
CORPORATION COMMISSION

DEC 14 1964

12-14-64
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. James W. Rockhold of Prairie Oil Field Services this
Inc.
date requested permission to plug the following described well:

Mr. James W. Rockhold guarantees payment of the plugging fee.

Operator's full Name: Prairie Oil Field Service

Complete Address: Box 797, Great Bend, Kansas

Lease Name: Zugg Well No. # 2

Location: NW SW NE Sec. 34 Twp. 16 Rgs. 13 (E) (W) W

County Barton Total Depth 3409 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

8 5/8" 276' Gwc.

Sanded hole back to 3010' & dumped 5 sax cement with
dump bailer. Pulled pipe. Mudded hole to 250'; set rock bridge;
displaced 25 sax cement. Mud to 40'; set rock bridge &
displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent