



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Catt of Kathol Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Catt guarantees payment of the plugging fee.

Operator's full Name: Kathol Petroleum Inc.

Complete Address: 900 Sutton Place Wichita, Ks

Lease Name: Olson A Well No. 1

Location: C SE/NW Sec. 4 Twp. 31s Rge. 12 (E)(W) W

County: Barber Total Depth 3800 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Catt was instructed to plug the well as follows:

270 ft of 8 5/8 surface pipe cemented with 200 sacks. Fill

hole to 260 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud

to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

H. Russell Chertier
Conservation Division Agent

12