

15-007-20020-00-00

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 8 1967  
5 8 67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed April 25, 1967.

Dear Sir:

Mr. Harold Burke of Shenandoah Oil Corp. has this  
date requested permission to plug the following described well:

Mr. Burke guarantees payment of the plugging fee.

Operator's full Name: Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Bldg., Fort Worth, Texas

Lease Name: McMlellan Trustee Well No. # 1

Location: 300' N of C of W/2 Sec. 16 Twp. 31 Rge. 10 (E)(W) W

County Barber Total Depth 4601' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burke was instructed to plug the well as follows:

281' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill  
hole with drilling mud to 270', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving  
Conservation Division Agent