

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 3 1963
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Joe Cain of Jones- Gebert Oil Inc. has this

date requested permission to plug the following described well:

Mr. Joe Cain guarantees payment of the plugging fee.Operator's full Name: Jones- Gebert Oil Inc.Complete Address: 1007 Central Bldg. Wichita, Kansas.Lease Name: Rankin #1 Well No. #1Location: C-SW-NE Sec. 12 Twp. 31S Rge. 10 (E) (W) XCounty Barber County Total Depth 4745' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Joe Cain was instructed to plug the well as follows:

216' of 8 5/8" surface pipe circulated with cement. Hole
filled to 180' with heavy drill mud, 1 sack hulls, 1st
cementing plug & 20 sacks cement. Hole filled to 40' with
heavy drill mud, 1 sack hulls, 2nd cementing plug & 10
sacks cement to base of cellar. Rat hole bridged and 2
sacks cement.

Very truly yours,

Harman Justers
 Conservation Division Agent