

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 20 1966

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Curley Brau of Edmiston Drilling Co. Inc. has this date requested permission to plug the following described well:

Mr. Baru guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Ks.

Lease Name: Warwick-Allender "B" Well No. # 1

Location: C NW SW Sec. 7 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4597' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

230' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Elving*