

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. R. B. McFarland of Solar Oil Company has this date requested permission to plug the following described well:

Mr. McFarland guarantees payment of the plugging fee.

Operator's full Name: Solar Oil Company

Complete Address: 1117 Union National Bldg., Wichita, Kans.

Lease Name: Stone Well No. # 1

Location: C NW NE Sec. 22 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4965 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. McFarland was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cemented with 200 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving
Conservation Division Agent