

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Hopkin of Aylward Drilling Co. has this date requested permission to plug the following described well:

Mr. Hopkin guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, KS.

Lease Name: Donovan "D" Well No. # 1

Location: C SE SW Sec. 11 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 5308 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hopkin was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 200
sacks. Fill hole with mud to 180', 1st cementing plug,
1/4 sack hulls, cement with 20 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/2 sack hulls, cement with
10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Arlene Elving
 Conservation Division Agent