

1 080227

15-007-21486-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Completed 9-23-82  
C NW SE, SEC. 15, T 31 S, R 12 W/E  
1980 feet from ~~XXX~~ section line  
1980 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5002  
Operator: George R. Jones  
Name & Address 125 North Market, Suite 1210  
Wichita, KS 67202

Lease Name Pike Well # 1  
County Barber  
Well Total Depth 4720 153.40 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: noon Day: 28 Month: September Year: 19 84

Plugging proposal received from Ken Gates

(company name) Pratt Well Service (phone) 1-800-362-0597

were: 4 1/2" set at 4665' PBD 4665' Perfs at 4302-10'

1st plug pump 1/2 sack hulls and 35 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 pm Day: 28 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4665' PBD 4665' Perfs at 4302-10'

1st plug pumped 1/2 sack hulls and 35 sx cement to bottom, 2nd plug squeezed well with

3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber

plug and pumped an additional 125 sx cement.

Maximum pressure 650 psi and shut in pressure 600 psi  
RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
OCT 05 1984

(If additional description is necessary, use BACK of this report)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 10-8-84

INV. NO. 4134  
9-28

Signed J. H. Metz  
(TECHNICIAN)