

1 040856

6-14

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,349-00-00

NW NW NW, SEC. 8, T 31 S, R 12 W/X  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30217

Lease Name Gress Well # 5

Operator: Robba Exploration, Inc.

County Barber 151.45

Name & Address 230 N. Market

Well Total Depth 4660 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 14 Month: 6 Year: 1994

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4659' w/150 sx cement, Perfs at 4328-4349, 4351-61'

1st plug sand back to 4275' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 17 1994

CONSERVATION DIVISION  
Wichita, Kansas  
Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:45 a.m. Day: 14 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pump 100 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel By Allied. Recovered 3100' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE 40641

Signed Stephen J. Pfeifer  
(TECHNICIAN)