

1040152

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,850 - 00-00

C W/2 NW NE, SEC. 10, T 31 S, R 12 W X

660 feet from N X section line

2310 feet from X E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5601

Lease Name Haas Estate Well # 7

Operator: Associated Petroleum Consult.
Name & Address Suite 600 - One Main Place
Wichita, KS 67202-1399

County Barber

Well Total Depth 4512 146.64 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Heartland Drilling, Inc. License Number 5867

Address Suite 600 - One Main Place, Wichita, KS 67202-1399

Company to plug at: Hour: 11:00 pm Day: 8 Month: July Year: 19 84

Plugging proposal received from Jack Kaiser

(company name) Heartland (phone) 316-265-9723

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 650' with 50 sx cement

2nd plug at 345' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Edgar M. Knobloch
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:00 am Day: 9 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 650' with 50 sx cement, 2nd plug at 345' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun # 19083
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 7-16-84

INV. NO. 2532
7-9

Signed Edgar M. Knobloch
(TECHNICIAN)