

To: 1 040666
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-24

API NUMBER 15- 007-22,135-00-00 159R

N/2 NW NE, SEC. 16, T. 31 S, R. 12 W/E
4950 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3667
Operator: Source Petroleum
Name & Address: 200 W. Douglas, Suite 820
Wichita, KS 67202

Lease Name Elliot C Well # 1
County Barber
Well Total Depth 4430 143.97 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 24 Month: 6 Year: 19 92

Plugging proposal received from Jeff Clarke
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4427' w/100 sx cement. PBTB 4389', Perfs at 4348-63'
1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 24 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 950 psi and shut in 800 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(Observe this plugging.)

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 7-17-92
INV. NO. 35695 OCT 28 1992
6-24