

3021208

960127

15.001.03342.00.00

24/R

9-14

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 WICHITA STATE OFFICE BLDG., 130 S. MARKET  
 WICHITA, KANSAS 67202  
 TECHNICIAN'S PLUGGING REPORT  
 OPERATOR LICENSE # \_\_\_\_\_  
 OPERATOR: STATE OF KANSAS  
 NAME AND FEE FUND PLUGGING  
 ADDRESS \_\_\_\_\_

API NUMBER 15- N/A  
 SE \_\_\_\_\_, SEC. 18, T 26 S, R 18 E  
1500 FEET FROM SOUTH SECTION LINE  
2500 FEET FROM EAST SECTION LINE (#5A)  
 LEASE NAME BURTISS WELL #OW14  
 COUNTY ALLEN  
 WELL TOTAL DEPTH 800 FEET  
 CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_  
 SURFACE CASING: SIZE 7 FEET N/A  
 ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL X SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_  
 PLUGGING CONTRACTOR FAITH DRILLING COMPANY LICENSE NUMBER 6023  
 ADDRESS P.O. BOX 816, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 26 MONTH: 7 YEAR: 96  
 PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL  
 (COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 1 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE SURFACE CASING WAS REMOVED LONG AGO. THE PLUGGING PROPOSAL WAS TO INSTALL 23' OF 7" SURFACE CASING AND TO FILL AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 1 1/2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL  
 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 5:45 PM DAY: 14 MONTH: 9 YEAR: 96  
 ACTUAL PLUGGING REPORT 23' OF 7" SURFACE CASING WAS WASHED OVER THE 1 1/2" CASING. 3/4" PIPE WAS WASHED INTO THE 1 1/2" CASING TO 540'. 1" WAS WASHED INTO THE 1 1/2" AND 7" ANNULUS TO 500'. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 3/4" AND 1 1/2" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1 1/2" AND 7" ANNULUS AT SURFACE. THE 1" AND 3/4" WERE SETTLAGES AND DISPLACEMENT WERE FILLED FROM SURFACE. 160 SACKS OF CEMENT WERE PUMPED

REMARKS: INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.  
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

SK (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel  
 (TECHNICIAN) FORM CP-2/3

RECEIVED  
 KANSAS CORP COMM  
 1997 OCT 3 1:03