

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22714-00-00  
Spot: SWNE Sec/Twnshp/Rge: 29-31S-10W  
2080 feet from N Section Line, 1980 feet from E Section Line  
Lease/Unit Name: MATTHEWS Well Number: 1  
County: BARBER Total Vertical Depth: 4243 feet

Operator License No.: 31514  
Op Name: THOROUGHbred ASSOCIATES L.L.C.  
Address: 8100 E. 22ND ST. - BUILDING 600  
WICHITA, KS 67226

Conductor Pipe: Size feet: 937.90  
Surface Casing: Size 8.625 feet: 355  
Production: Size feet:  
Liner: Size feet:

Well Type: LH UIC Docket No: Date/Time to Plug: 10/12/2002 8:00 AM

Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.

Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 3700' WITH 50 SX CMT. 2ND PLUG AT 3000' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 380' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 10/12/2002 1:00 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 3700' WITH 50 SX CMT. 2ND PLUG AT 3000' WITH 50 SX CMT. RUN 4 1/2" CASING TO 600' WITH CUT SLOTS ON BOTTOM JOINT. RAN 3 CMT BASKETS ON BOTTOM JOINT. ONE CMT BASKET AT 1ST COLLAR, 1 BASKET AT 300'. CIRCULATED CMT TO SURFACE. A TOTAL OF 300 SX CMT WAS USED. CIRCULATED 15 SX CMT IN RATHOLE.


RECEIVED  
OCT 17 2002  
KCC WICHITA

Remarks: USED CLASS A 3% CC BY ALLIED.

Plugged through: DP

District: 01

Signed

  
(TECHNICIAN)

INVOICED OCT 14 2002

DATE 10-18-02 

WV. NO 2003060657

Form CR-2/3 