

1 040405

2-26

-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,408-A

N/2 SW NW, SEC. 33, T. 31 S, R. 10 W/E

3630 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3248

Lease Name 3-1 Amsden Well # 1-B

Operator: Masters Operating Company  
Name & Address: 240 North Rock Road, Suite 135  
Wichita, KS 67206

County Barber 145.60

Well Total Depth 4480 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 26 Month: 2 Year: 1990

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 600'

1st plug at 600' with 50 sx cement, 2nd plug at 380' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 26 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 380' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED  
DATE 3 FEB 28 1990

Signed Stephen J. Puffer (TECHNICIAN)

INV. NO. 27590 Kansas

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 01 1989  
month day year

N 1/2 SW 1/2 NW 1/2 Sec 33 Twp 31 S, Rg 10 East  
3630 feet from South line of Section  
4620 feet from East line of Section  
(Note: Locate well on Section Plat Below)

OPERATOR: License # 3248  
Name: Masters Operating Company  
Address: 240 N. Rock Rd. #135  
City/State/Zip: Wichita, KS 67206  
Contact Person: Robert T. Stolze  
Phone: (316) 682-8844

County: Barber  
Lease Name: 3-1 Amsden Well #: 1-B  
Field Name: None

CONTRACTOR: License # 5929  
Name: Duke Drilling Co., Inc.

Is this a Prorated Field? yes X no  
Target Formation(s): Douglas/Mississippian  
Nearest lease or unit boundary: Carter Gas Unit NW 1/4 NW 1/4 Sec. 33  
Ground Surface Elevation: 1642 feet MSL

Well Drilled For: Well Class: Type Equipment:  
X Oil Inj Infield X Mud Rotary  
X Gas Storage Pool Ext Air Rotary  
X OAWO Disposal X Wildcat Cable  
Seismic; # of Holes

Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 180'  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe set: 351'

If OAWO: old well information as follows:  
Operator: George R. Jones  
Well Name: Amsden #1  
Comp. Date: 3/15/82 Old Total Depth: 4484'

Length of Conductor pipe required:  
Projected Total Depth: 4484'  
Formation at Total Depth: Mississippian Osage  
Water Source for Drilling Operations:  
... well X farm pond ... other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, total depth location:

DWR Permit #:  
Will Cores Be Taken? yes X no  
If yes, proposed zone:

AFFIDAVIT

351' Alt. I Req.

PUSHER John Armbuster

TD 4480 FORMATION M.S.S.

SURFACE PIPE 2 1/2" @ 351'

ANHYDRITE 600 ELEVATION

STARTING TIME & DATE 12:30p 2-26-90

COMPLETION TIME & DATE 2:00p 2-26-90

1st PLUG @ 600 FT. W/ 50 SX

2nd PLUG @ 380 FT. W/ 40 SX

3rd PLUG @ 46 FT. W/ 10 SX

4th PLUG @ FT. W/ SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ 10 SX

WATER WELL PLUGGED W/ SX

CEMENT COMPANY Allied

TECHNICIAN S.P. 2-26-90

TYPE OF CEMENT 60/40 6070

Spud 2-23-90  
In place 351' x 8 1/8"  
W.W. = NO

Vertical scale with markings from 330 to 1650.

FEB 28 1990

Mail to: Conservation Division, 200 Colorado Derby Building, 202 W. First St., Wichita, Kansas 67202-1286.

Conservation Division  
Wichita, Kansas

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.

CHERYL DENOIT

(Signature)

Handwritten signature