

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01088-00-00
Spot: CSWNENW Sec/Twnshp/Rge: 12-34S-13W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: DONOVAN Well Number: 1
County: BARBER Total Vertical Depth: 4775 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 275
Production: Size 5.5 feet: 4775
Liner: Size _____ feet:

\$155.19

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2001 5:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: BRAD TATRO Company: PRATT WELL SERVICE, INC. Phone: (316) 672-2531

Proposed Plugging Method: SAND BACKT TO 4600' & 5 SX CMT. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/14/2001 6:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4775'. PERFS AT 4666-93, 4705-30'. SANDED BACK TO 4580' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. LOAD HOLE WITH 10 SX GEL & SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1995' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

SEP 20 2001

KCC WICHITA

INVOICE

SEP 17 2001

DATE 9-21-01

INV. NO. 2002060560

Form CP 3/2