

1060256

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,846 -00-00
NE/4, SEC. 11, T 34 S, R 13 W ~~XX~~
1090 feet from ~~NXX~~ section line
880 feet from ~~WXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Donovan E Well # 1

Operator: Molz Oil Company

County Barber

Name & Address R. R. 2, Box 54

Well Total Depth 5250 ^{170.63} feet

Kiowa, KS 67070

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 267 ²⁹⁰

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address 500 Heritage Park Place, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 2 Month: July Year: 1984

Plugging proposal received from Floyd Hildreth

(company name) Sweetman (phone) 316-265-5561

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 600' with 50 sx cement

2nd plug at 310' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15 am Day: 2 Month: July Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement, 2nd plug at 310' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(if additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 7-18-84

INV. NO. 2558

7-2