

1 040565

9-13

74 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-007-21,962-00-00
120' W of C. NE SW, SEC. 16, T. 34 S, R. 13 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: Marathon Oil Company
Name & Address: 7301 N.W. Expressway
Oklahoma City, OK 73132

1980 feet from S section line
3420 feet from E section line

Lease Name Diel B Well # 1
County Barber 155-35
Well Total Depth 4780 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address 107 Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 9 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4779' w/175 sx cement, PBTD 4755', Perfs at 4574-78'

1st plug sand back to 4520' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 13 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4520' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 250 psi.

RECEIVED
CORPORATION
SEP 18 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if you observe this plugging.)

DATE 10-4-91

INV. NO. 33266

Signed [Signature] (TECHNICIAN)