

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20952-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 2-32S-35W  
4950 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: BROLLIER A Well #: 2  
County: STEVENS Total Vertical Depth: 6177 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	6176	2010	WITH 175 SX CMT
SURF	8.625	1733		WITH 580 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2013 12:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 200# HULLS. PLUG AT 1760' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/21/2013 6:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

COULD ONLY GET TBG TO 5806'. PUMPED 40 SX CMT. TAGGED CMT AT 5463'.  
1ST PLUG AT 1770' WITH 50 SX CMT. 2ND PLUG AT 610' WITH 50 SX CMT. 3RD  
PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6050	6060		


Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

RECEIVED  
DEC - 3 2013  
KCC DODGE CITY

Signed

  
(TECHNICIAN)  
✓ 12/20/2013

KCC WICHITA  
DEC 09 2013  
RECEIVED

Form CP-2/3

