

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
AIVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Sullivan of Sierra Petroleum Co. Inc. has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Sullivan Petroleum Company, Inc.

Complete Address: 1015 Wichita Plaza Bldg., Wichita, Kans.

Lease Name: McReynolds Well No. # 1

Location: C SW SE Sec. 30 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4626' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

210' of 8 5/8" surface pipe cement circulated with 185 sacks.
Fill hole with drilling mud to 210', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent