

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10807-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 27-21S-14W
337 feet from S Section Line, 2309 feet from E Section Line
Lease Name: PILE Well #: 1
County: STAFFORD Total Vertical Depth: 3803 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3480		WITH 2 SX CMT
PROD	5.5	3793	0	WITH 200 SX CMT
SURF	8.625	416		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2013 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2962

Proposed Plugging Method: SET CIBP @ 3480' WITH 2 SX CMT. PERFORATE 5 1/2" CASING AT 900'. RUN TBG BELOW 900' & CIRCULATE CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2013 12:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3480' WITH 2 SX CMT ON TOP WITH DUMP BAILER. PERFORATED 5 1/2" CASING AT 900'. RAN TBG TO 918'. PUMPED 375 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2" CASING AND THE 8 5/8" X 5 1/2" ANNULUS. PULLED TBG OUT OF HOLE. TOPPED OFF WELL WITH 25 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4	3531		

KCC WICHITA
DEC 06 2013
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
DEC - 3 2013
KCC DODGE CITY

12/20/2013