

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19232-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 19-14S-14W  
1700 feet from S Section Line, 3000 feet from E Section Line  
Lease Name: REINHARDT Well #: 7  
County: RUSSELL Total Vertical Depth: 3245 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3244		200 SX
SURF	10.75	869		525 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/27/2013 12:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: JOE Company: AWI Phone: (620) 275-2963

Proposed Plugging Method: Open Hole Arbuckle: 3244' - 3245'.  
Ordered 450 sx 60/40 pozmix 4% gel cement w/900 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2013 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Bridge at 1421'. Drilled to 1681'. Started to lose circulation on 7" casing but started circulating out the backside of the 10 3/4" surface pipe. Ran tubing to 1665'. Swift pumped 100 sx cement followed by 175 sx cement w/600 # hulls. Pulled tubing to 832' and pumped 150 sx cement w/300 # hulls. Circulated cement out 7" casing. PTOH. Topped off 7" casing w/25 sx cement. Backside Equalized. Will tag cement Monday.  
12/02/2013- Cement 80' down. Case approved. Topped off w/redimix.  
12/04/2013- Dug out 10 3/4" and 7" casing and filled with 1.5 gal redi mix. Both 7" and 10 3/4" casings are full.

Perfs:

Top	Bot	Thru	Comments
3244	3245		

**KCC WICHITA**

Remarks: SWIFT

DEC 09 2013

Plugged through: TBG

RECEIVED

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

12/20/2013

DEC 05 2013