

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21753-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 27-34S-5W
115 feet from N Section Line, 150 feet from W Section Line
Lease Name: SEIFERT Well #: 1-27
County: HARPER Total Vertical Depth: 5355 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5352	3059	340 SX
PROD	5.5	5355		340 SX
SURF	8.625	348		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: _____

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 11/20/2013 5:50 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @4650' CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3059' PULLED CASING TO 2850' SPOTTED 50 SX CEMENT WITH 3% CC BECAUSE WELL WAS FLOWING BACK. PULLED CASING TO 970' SPOTTED 40 SX CEMENT. PULLED CASING TO 670' SPOTTED 60 SX CEMENT, TAGGED TOC AT 550'. PULLED CASING TO 410' CIRCULATED TO SURFACE WITH 170 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4900	4987		
4783	4790		
4763	4774		
4754	4757		
4715	4720		
4693	4790		

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40 4% POS MIX, TICKET #40751

Plugged through: CSG

District: 02

Signed

BT Hope

(TECHNICIAN)

✓ 12/20/2013

✓ JK

KCC WICHITA

DEC 13 2013

RECEIVED