

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23806-00-00  
Spot: SENESWSW Sec/Twnshp/Rge: 21-16S-21W  
665 feet from S Section Line, 999 feet from W Section Line  
Lease Name: CHAFF UNIT Well #: 6  
County: NESS Total Vertical Depth: 4340 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1628		WITH 638 SX CMT
PROD	5.5	4342	0	WITH 300 SX CMT
SURF	8.625	308		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2013 10:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: BOTTOM PLUG: PUMP 50 SX CMT & 150# HULLS. PLUG AT 2850' WITH 50 SX CMT & 150# HULLS. PLUG AT 1628' TO SURFACE WITH CMT. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/20/2013 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4142' & PUMP 50 SX CMT & 150# HULLS. CASING WAS PARTED AT 2868'. PULLED TBG TO 2868' & PUMPED 50 SX CMT & 150# HULLS. PULLED TBG TO 1615' & PUMPED 185 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 40 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4234	4245		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA  
DEC 04 2013  
RECEIVED

District: 01

Signed Michael J. Maier  
(TECHNICIAN)

12/20/2013

RECEIVED  
NOV 26 2013  
KCC DODGE CITY