

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name: Gress "B" Well No. # 1

Location: C NE SE Sec. 18 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 3777' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

264' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 260', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent