

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Budig of Union Drlg Co has this

date requested permission to plug the following described well:

Mr. Budig guarantees payment of the plugging fee.

Operator's full Name: G.N. Rupe

Complete Address: 200 W Douglas Wichita, KS

Lease Name: Gress Well No. 1

Location: NE/NE/SW Sec. 8 Twp. 31s Rge. 12 (E)(W) W

County: Barber Total Depth 3695 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Budig was instructed to plug the well as follows:

289 ft 8 5/8 surface cemented with 250 sacks. Pump plug,
30 sacks cement to 270 ft. Mud to 40 ft, plug, 1/2 sack
hulls, 15 sacks cement to surface. 2 sacks cement in
rat hole.

Pumped by Allied Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent