

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

MAY 14 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Elmer Rider of K & E Drilling Co. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling Co.-W. J. Coppinger

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name: Inslee Well No. # 1

Location: C NW SW Sec. 18 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4556 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

232' of 8 5/8" surface pipe, cement circulated with 175  
sacks. Fill hole with mud to 180', 1st cementing plug,  
1/2 sack hulls, cement with 20 sacks. Fill hole with mud to  
40', 2nd cementing plug, 1/4 sack hulls, cement with 10 sacks  
to base cellar. Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent