

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21090-00-00
Spot: E2SE Sec/Twnshp/Rge: 36-9S-20W
1320 feet from S Section Line, 660 feet from E Section Line
Lease Name: PYWELL Well #: 2
County: ROOKS Total Vertical Depth: 3905 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3904		140 SX
SURF	8.625	189		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WILLIAM F. BOWMAN Company: BILL BOWMAN OIL CO. Phone: (785) 259-1297

Proposed DV Tool at 1660' with 450 sx cement.
Plugging Production perforations: 3786' - 3788'
Method: Casing leak at 1968' - 2097'
Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2013 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3006'. Allied pumped 150 sx cement w/300 # hulls. Pulled tubing to 1700'.
Allied pumped 125 sx cement w/300 # hulls. Cement circulated. PTOH. Topped 4 1/2" casing
w/30 sx cement. Casing full. Hooked up to backside with instant pressure at 1000 psi.

Perfs:

Top	Bot	Thru	Comments
3786	3788		
3647	3649		
3637	3639		

Remarks: ALLIED
Plugged through: TBG

KCC WICHITA

DEC 09 2013
RECEIVED

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

12/20/2013

Form CP-2/3

DEC 05 2013