

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00928-00-00
Spot: N2SESW Sec/Twnshp/Rge: 19-17S-9W
1009 feet from S Section Line, 3326 feet from E Section Line
Lease Name: SPLITTER B Well #: 2
County: ELLSWORTH Total Vertical Depth: 3242 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3239		
SURF	8.625	181		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2013 2:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMAN Company: CARMEN SCHMITT INC. Phone: (620) 793-2540

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 12/04/2013 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

UNKNOWN TO KCC, THIS WELL HAD BEEN PRODUCING UNDER PACKER. FORMATION FELL IN ON PACKER, AND OPERATOR COULDN'T PULL IT OUT. TRIED WASHOVER PIPE - STILL UNSUCCESSFUL. TRIED MILLING OUT PACKER FOR 3 DAYS - STARTED GETTING SALT INFORMATION OUT--STILL UNSUCCESSFUL. WEATHER STARTED GETTING COLD -- EMERGENCY PLUGGING REQUEST GRANTED. RUN IN TUBING TO 2960' (TOP OF FISH), AND PUMP 35 SX'S CEMENT. PERFORATE AT 1225', 925', AND 250'. RUN TUBING TO 1225' AND PUMP 35 SX'S CEMENT WITH 3% CC AND 50#'S COTTON HULLS, LET SET AWHILE--TAGGED AT 1220'. PULL TUBING TO 925' AND PUMP 35 SX'S CEMENT WITH 3% CC AND 50#'S COTTON HULLS, LET SET AWHILE--TAGGED AT 885'. PULL TUBING TO 250' AND CIRCULATED CEMENT TO SURFACE, (40 SX'S). CONNECTED ON TO SURFACE CASING AND PUMPED 15 SX'S -- PRESSURED UP TO 250-- HELD PRESSURE @ 100. USED APPROX. 160 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3239	3242	OH	

Remarks: CLASS A CEMENT. LOG TECH OF KS #7723. ALLIED TICKET #61041 ON 12-3. & 61042 ON 12-4.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

12/20/2013

JK

KCC WICHITA

Form CP-2/3

DEC 13 2013

RECEIVED